

Pearl River Solar Farm | Mississippi

Utilization of BaseLok® FabGrid®
in Lieu of Lime Stabilization |
Mechanical Stabilization

PROJECT TEAM

OWNER:

EDP Renewables

ENGINEER:

NDA

JOB NUMBER:

N/A

CONTRACTOR:

Tindol Construction Services

SUPPLIER:

Industrial Fabrics, Inc. (IFI)

TECHNICAL DESCRIPTION:

Product: BASELOK® FabGrid®

Square Feet: 180,000 yd²

Installation Date: Fall of 2021

Completion Date: Fall 2023



PROJECT DESCRIPTION:

A heavily forested 1,760 Acre Solar Development located in Scott County, MS. Roads and laydown areas needed to be constructed to support construction activities for this massive project, which would span over two years.

PROBLEM:

Weak soil sub-grades would not support heavy-truck and construction traffic. This challenging site experienced significant equipment rutting during logging and deforestation operations. Additionally, extreme flooding from the nearby Pearl River, exacerbated rutting and pumping of sub-grade material. Construction schedules were delayed due to poor site conditions.

SOLUTION:

BaseLok® FabGrid® FG6 Geocomposite was chosen to reinforce aggregate base material. Base material was placed and compacted on top of the stiff BaseLok® FabGrid® FG6 with tremendous results. No delays were incurred during spring rains in 2023, construction dates were not further impacted.